Lake Decatur Basins 1 through 4 Dredging Project Fact Sheet




Background

Lake Decatur was constructed on the Sangamon River as a public water supply reservoir in 1920-1923. Since then natural and human caused erosion severely reduced the lake's storage capacity. The lake is separated by bridges into six large basins. Basin 5 was reclaimed by dredging in 1993-1994 and Basin 6 in 2004-2011. The dredging of Basins 1 through 4 began in 2014 and will continue through 2019.

Project Details

Great Lakes Dredge and Dock Company operates a cutter head suction dredge named "LW" that hydraulically removes Lake Decatur accumulated sediment. The dredge produces a slurry of 10 to 15% sediment and 85 to 90% lake water that is pumped through a 24 inch diameter pipeline and pumping station system to the City's Sedimentation Basin located in Oakley Township east of Basin 5. In the basin, gravity causes the sediment to settle out of the lake water. Clean lake water is then returned from the storage basin to Lake Decatur by an unnamed creek.

The project will increase the lake's storage capacity by 30% or 52 days of additional water supply for our community. This is equivalent to the volume of over 60 Willis (formerly Sears) Tower skyscrapers located in downtown Chicago! Sediment traps will be created in Big Creek and Sand Creek to capture incoming sediment before it reaches the main body of the lake. A sediment trap was previously constructed in Basin 6. Below is a map outlining the areas to be dredged in black with average water depth increases after dredging is completed.



Schedule

February 2014 Dredging contract approved by Decatur City Council

March 2014 Contractor begins rehabilitating the Oakley Sedimentation Basin April 2014 Contractor begins dredging equipment mobilization and assembly

November 2014 Basin 1 dredging begins 2015 Big Creek dredging begins

2016 Sand Creek and Basin 2 dredging begins

2018 Basin 3 dredging begins

2019 Basins 4 and 6 dredging begins

December 2019 Project completion

Cost & Funding

 Design
 \$ 1,132,478

 Construction
 \$ 89,504,536

 Construction Administration
 \$ 766,522

 Miscellaneous Expenses
 \$ 40,000

 Total Cost
 \$ 91,443,536



The project is funded by the sale of drinking water and raw Lake Decatur water by the City of Decatur and financed through 20 year term bond issuances. Additional funding is provided by the Archer Daniels Midland Company.

Project Partners

Owner City of Decatur, IL

Contractor Great Lakes Dredge and Dock, Rivers & Lakes Division

St. Peters, MO

Major Subcontractor Terra Contracting Services, Kalamazoo, MI

Design Services & Chastain & Associates, Decatur, IL

Construction Administration

Geotechnical Services SKS Engineers, Decatur, IL

Primary Regulatory Agencies U.S. Army Corps of Engineers, Rock Island, IL

Illinois Environmental Protection Agency, Springfield, IL

For More Project Information

Contact the Water Management Department at (217) 424-2863.

For More Lake Decatur and Boating Safety During Dredging Information

Contact the Lake Office at (217) 424-2837.

- Boaters are urged to exercise extreme caution on Lake Decatur.
- Dredge can be contacted on VHF-FM channel 13 and 16.
- Avoid all buoys, dredge equipment and please observe the warning signs on the lake.